

# Lab Cisco Switch - QOS testing (April 13, 2022)

## Setup:

Two (2) Cisco switches isolated and connected via Trunk Port.

MW Link setup between the 2 Cisco switches to be able to reduce network bandwidth and test QOS.

MW Link has a max bandwidth of 169 Mbps.

All Cisco ports operating on 1Gbps.




Figure 1

## TEST 1: Oversubscribe Queue 3 to 60 Mbps

**Step 1: Test traffic** - 4 streams of 42.25 Mbps each from each Tester = 169 Mbps (limit of the MW radio).  
See Figure 2.

### Streams:

VLAN 300 / Pri 6 = 42.25 Mbps (Strict Priority-LLQ Low Latency Queue /10% of bandwidth)

VLAN 44 / Pri 5= 42.25 Mbps (Queue 2/ 47% of bandwidth)

VLAN 72 / Pri 4= 42.25 Mbps (Queue 1/ 29% of bandwidth)

VLAN 11 / Pri 2=42.25 Mbps (Queue 0/ 14% of bandwidth)




Figure 2.

**Step 2: QOS Test** - Queue 3 (Stream 1 – VLAN 300) is oversubscribed to 60 Mbps.

**Result:** See Figure 3

Queue 3 correctly passes the 60 Mbps.

Tester 2 → Tester 1: Throughput reduced on Queues 1 and 0

Tester 1 → Tester 2: Throughput reduced on Queues 1 only



Figure 3.

## TEST 2: Oversubscribe Queue 3 to 150Mbps

**Step 1: Setup:** Same as Test 1

**Step 2: QOS Test - Queue 3** (Stream 1 – VLAN 300) is oversubscribed to 150 Mbps.

**Result:** See Figure 4

Queue 3 does not receive the entire 150 Mbps in both directions.

Tester 2 → Tester 1: Throughput reduced on Queues 1 and 0

Tester 1 → Tester 2: Throughput reduced on Queues 1 only



Figure 4.

**TEST 3: Reduce network link throughput (MW link); Cisco ports at 1Gbps.**

**Step 1: Setup :** Same as TEST 1 (Queue 3 is restored to 42.25 Mbps.)

**Step 2: QOS Test -** The MW Link is attenuated to reduce link bandwidth between the 2 Cisco switches to 141-144 Mbps.

**Results:** See Figure 5.

Queue 3 correctly retains 42.25 Mbps.

Tester 2 → Tester 1: Throughput reduced on Queues 1 and 0

Tester 1 → Tester 2: Throughput reduced on Queues 1 only



Figure 5.

**TEST 4: Reduce network link throughput (MW Link); Cisco ports at 100Mbps.**

**Step 1: Setup:** Cisco Ports set to 100 Mbps.

**Step 2: Test traffic** - 4 streams of 25 Mbps each = 100 Mbps (limit of the Cisco ports).

**Streams:**

VLAN 300 / Pri 6 = 25 Mbps (Strict Priority-LLQ Low Latency Queue /100% of bandwidth)

VLAN 44 / Pri 5= 25 Mbps (Queue 2/ 0% of bandwidth)

VLAN 72 / Pri 4= 25 Mbps (Queue 1/ 0% of bandwidth)

VLAN 11 / Pri 2= 25 Mbps (Queue 0/ 0% of bandwidth)

See Figure 6




Figure 6

**Step 3: QOS Test** - MW Link attenuated to force a lower modulation with 43 Mbps throughput.

**Results:** See Figure 7.

Queue 3 correctly retains 42.25 Mbps.

Tester 2 → Tester 1: Throughput on Queues 1 and 0 reduced to 0.

Tester 1 → Tester 2: Throughput on Queue 1 reduced to 0.




Figure 7